



7x12 Fiber Splicing Trailer

Model Fiber Splicing **GVWR** 7000

Weight 3000 **Payload Capacity** 4000

Axle Capacity 3500

Color White **Width Total** 84

Axles 2 **Pull Type** Bumper

Nose Type Flat **Roof Type**

Aluminum Skin **Side Wall Height** 84in / 7ft

Key Features in Fiber Trailer

- Turnkey trailer loaded with everything you need
- 7x12
- 3500 lb. axles with electric brakes
- Steel deck platform
- .080 exterior siding
- Blackout trim package
- 1 pc. aluminum roof
- 6" main frame tubing
- 7' interior height
- 5000 lb. jack
- 15x30 windows in both doors
- 30x30 windows on each side
- 8 LED flood lights in the exterior
- 2 amber strobe lights
- Emergency directional light
- RV pull-out step under side door
- Steel rear step across entire trailer
- Insulated walls and ceiling
- White aluminum walls and ceiling
- Rubber coin floor
- 50-amp electrical package with plenty of LED ceiling lights and outlets
- 15k air conditioner with a heat pump
- 40" base cabinets so you can work standing up or sitting
- Two drawer banks in base cabinet
- Upper cabinet
- Pull-out trashcan
- Microwave
- Stereo with 4 speakers mounted in ceiling
- Extra tall office chair
- Fire extinguisher

- Carbon monoxide detector
- First aid kit
- Eyewash station
- 7250-watt Gen Max inverter dual fuel generator
- Automatic transfer switch so you don't have to run a cord to generator
- 100 lb. propane tank with cage
- Mounted spare tire



PSI

Jeff Matson - Regional Manager

Corporate Headquarters: Mahwah, NJ

My office: Clearwater, FL

Cell 727-793-1010

jeff@psitec.com

www.psitec.com